



Hervey Bay Presbyterian Church



Metcalfe Constructions were engaged as Construction Managers to facilitate the fast track the new hall extension for the Presbyterian Church. Care was observed where the new building abutted the existing church with careful and considerate planning required minimising any disruption to church services.

The project required refurbishment of an existing church, toilets and surrounding buildings for use by the Church Pastor and the construction of the new hall for use by the congregation. Building work comprised of alteration and extension to the existing Presbyterian Church. Construction included a new hall, offices, toilets/amenities, storerooms and a small commercial kitchen to serve the new hall.

The new extension was constructed of a reinforced clay block, timber frame with a colorbond cladding. The front of the new hall has a patio/courtyard enclosed by a curved timber wall frame lined with colorbond. The roof over the courtyard was curved structural steel and timber cut to match.

Metcalfe Constructions worked closely with the church as the demolition of existing toilet block and connection on the new hall to the pre existing structure were conducted.

The Church also received ducted air conditioning throughout, new colourbond roof and a new rear access concrete driveway. The project was delivered on time and on budget, with the building passing very stringent acoustic testing and certification criteria.

The grand opening was held on Saturday the 22nd November, with overwhelmingly positive responses from both the client and public alike.

Location	5 Denman Camp Road Scarness
Architect	Brown, Evans and Associates
Engineers	Holmes McLeod
Project	Extension to Hall and Toilet Block
Contract Value	\$708,000.00
Completed	October 2009

P 07 4128 2423 F 07 4191 4978
E info@metcalfeconstructions.com.au



QBSA Act Licence No. 1072636